



PVS-Hauptverwaltung, Mülheim an der Ruhr

Data and facts

Company

PORR Hochbau West GmbH

Type

Office buildings

Runtime

09.2023 - 08.2024

Principal

Privatärztliche Verrechnungsstelle(PVS)

[Project report online](#)

www.porr-group.com



PORR builds shell for new PVS headquarters

Prefabricated parts reduce construction time

Before the actual shell construction work could begin, a chiselling excavator had to loosen the rock in the building ground. Once it had completed the excavation for the haunches, lift underpasses and underground pipes, the foundation and basement were completed.

Due to the high groundwater level, the outer walls of the basement were constructed conventionally using watertight in-situ concrete. The construction of the other storeys will combine in-situ concrete work and prefabricated columns. Due to the very tight schedule, filigree walls are being used in the interior, and many of the columns and staircases are being constructed as precast elements.

The strict environmental regulations of the 'city by the river' are also a constant companion on the construction site. Following organoleptic testing, the groundwater was discharged into the public sewage system via sedimentation tanks. In addition, the water compatibility of the hydraulic fluids and lubricants used in the construction site vehicles had to be verified.

Impressions



Image notes

1

PVS-Hauptverwaltung, Mülheim an der Ruhr

PORR builds shell for new PVS headquarters in Mülheim an der Ruhr

Do you have questions about the project or would you like to learn more? Feel free to contact us for further information.

PORR AG Group Communications

Absberggasse 47

1100 Wien

T +43 50 626-0

E-Mail: comms@porr-group.com