



Restoration of buildings 93 & 94 in Camp Del Din, Vicenza

Data and facts

Company

Type Office buildings, Building service

Runtime 11.2015 - 10.2019

Principal US Army Corps of Engineers

[Project report online](#)

www.porr-group.com



BBGS transforms historic building into AFRICOM Headquarters.

The structural work involved building both ordinary (beams and plinth) and special (piles and micro piles) foundations, and horizontal and vertical construction (frames, slabs, sloped concrete roof, concrete walls, beams and columns). Both facilities are covered by flat and sloped roofs of clay tiles with waterproofing membranes, insulation and flashing. Most of the internal walls are drywall with insulation, but some are exposed brick. There are mixture of acoustic ceilings, gypsum board ceilings, and plaster painted ceilings with ceramic tile, carpet and vinyl floors throughout the interior.

Both building's internal and external closures were composed of Fire Protection Doors, ordinary Metal and Wood doors, Security doors, Aluminum and Metal windows, Anti-blast windows, metal grids and the related hardware. The project also included ordinary and ADA bathrooms, kitchens, drinking fountains, and metal works such as external metal stairs, handrails and beams.

Impressions



Image notes

1

Completely entrenched.

Building 94 was completely demolished and overhauled except for the outer walls.

2

Structurally reinforced.

Work was carried out on both buildings to reinforce the building structure with micro piles. In addition, a new floor was built in building 94 as part of the contract.

3

Successfully completed.

After a four-year project, both buildings were handed over to the client, the US Army Corps of Engineers.

Do you have questions about the project or would you like to learn more? Feel free to contact us for further information.

PORR AG Group Communications

Absberggasse 47

1100 Wien

T +43 50 626-0

E-Mail: comms@porr-group.com