

Stabilisation of a historic city wall, Aachen

Data and facts

Company	PORR Spezialtiefbau GmbH
Туре	Rehabilitation
Runtime	02.2022 - 05.2022
Principal	Eurovia Beton GmbH, Hofheim-Wallau

Project report online



Injection work for masonry renovation

In this way, PORR guaranteed reliable realisation at a consistently high level.

Stability restored

The grouting work was carried out from February to May 2020. The scope of work included reinforcing the ground-side wall area with injections once the masonry structure had been restored. Six pumps were used to inject a cement mixture through 130 boreholes in order to close cavities and consolidate the old masonry. The injections made the entire wall cross-section structurally effective again

Impressions



Image notes

1

Rehabilitation of the bank retaining wall in Aachen

Do you have questions about the project or would you like to learn more? Feel free to contact us for further information.

PORR AG Group Communications

Absberggasse 47 1100 Wien

T +43 50 626-0

E-Mail: comms@porr-group.com